

ALASKA LEGISLATURE COMPLETES, 2003 2000 80/2

11973 SENATE RESOURCES




Figure 11. Summary of Weld Packs on Cross-Country Lines on Pads – number of weld packs inspected, number of weld packs corroded, and percent of weld packs corroded.

Figures 11 and 12 depict the results of the major focus of the external weld pack inspection program in 2001. The cross-country on-pad weld packs were inspected using a prioritization scheme based on the historical corroded to wet ratios of the over-tundra portions of the cross-country lines. The well line weld packs were inspected using a prioritization scheme that examined the oldest, the hottest, and thinnest-walled lines first. Based on the results in Figure 12, it appears that the worst weld packs have been inspected and the risk of a future leak has been minimized. Continued inspections in 2002 will confirm if this hypothesis is correct. As of Year-End 2001, 61% of the cross-country on-pad weld packs and 43% of the well line weld packs have received their baseline TRT inspection.




Figure 12. Summary of Weld Packs on Well Lines – number of weld packs inspected, number of weld packs corroded, and percent of weld packs corroded.

3.1.e Below Grade Piping Program

In 2001, ADEC and Phillips Alaska, Inc., agreed to consolidate the Below Grade Piping Program report with the Commitment to Corrosion Monitoring Report. This section details the inventory and survey of below grade locations and the results of Specialty Testing. The plans for future inspections are given in section 3.2.e.

The Alaska Department of Environmental Conservation (ADEC) regulations under 18 AAC 75.080 apply to the Kuparuk oilfield facilities operated by Phillips Alaska, Inc. (PAI). To meet the requirements of 18 AAC 75.080, PAI submitted their corrosion control program for below-grade piping in early 1998. The program also included a field-wide inventory of all below-grade piping in the Kuparuk field. ADEC approved the program in written correspondence dated October 26, 1998.

3.1.e (1) Inventory and Survey of Below Grade Locations

PAI has 431 locations of below grade "oil" piping in the GKA oil fields. Of these, one is contained in a utilidor. The remaining locations are cased lines, the majority of which are either road or caribou crossings. In addition to the "oil" piping, PAI has 210 significant below grade locations with lines in other services.

Utilidor Line

Inspection Status:

The one line in a utilidor was inspected in 1999 and the results were reported in 2000.

Cased Lines

Inspection Status:

The annual visual survey of all the cased lines was conducted in 2001. The purpose of the survey was to identify, rectify, and report local conditions (e.g., debris found in casings and culverts, pipe insulation in contact with soil) that require remedial action.

Results and Remedial Action:

Of all the below-grade oil lines, 52 locations were found to have pipe in direct contact with soil and/or gravel/soil or debris in the casing. Of the 52 locations requiring remediation, the Corrosion Inspector cleaned 40 locations. Twelve other locations required more extensive gravel work by others; these 12 locations were cleaned by the Roads and Pads group and reinspected by the Corrosion Inspector.

3.1.e (2) Results of Specialty Testing

Inspection Status:

In 2001, both the long-range ultrasonic system technology from The Welding Institute (TWI) and the electromagnetic wave pulse system from Profile Technologies, Inc. (PTI) were used. Testing with PTI was limited to those lines without a significant risk for internal corrosion. PTI is used to find external electromagnetic anomalies such as external corrosion, but cannot find internal corrosion. The TWI technology was applied to lines with a risk for internal corrosion. TWI was also used to evaluate any positive indications detected by PTI, since PTI finds electromagnetic anomalies and is prone to finding false positives.

In addition to using TWI's long-range ultrasonic system technology, PAI evaluated the guided-ultrasonic (GUL) inspection technique from MQS-Cooperheat. PAI has determined that the GUL technique is not superior to the TWI long-range ultrasonic system and PAI will not use the GUL technique unless further improvements are made.



Results and Remedial Action:

Tables 4 and 5 show the results of the specialty testing performed by PTI and TWI, respectively.

Table 4. Results from the PTI inspections by service.

Service	Number of Cased Pipes Inspected	Number without any Electromagnetic Anomalies (N)	Number of Electromagnetic Anomalies (E)	Number of Significant Electromagnetic Anomalies (S)
Oil ^(a)	88	71	15	2
Other	106	87	18	1
Total	194	158	33 ^(b)	3 ^(b)

Notes:

(a) Oil service is defined as natural gas liquids, oil sales, three-phase production, two-phase production (wet oil), Produced Water, and Mixed Water.

(b) All "S" and "E" locations were inspected with TWI, except for two pipes with "E," the results of which were received after TWI had left the North Slope. These will be inspected with TWI in 2002.

Table 5. Results from the TWI inspections by service.

Service	Number of Cased Pipes Inspected	Inconclusive Results (I)	Number without any Significant Indications (N)	Number of Minor (Low) Anomalies (L)	Number of Moderate Anomalies (M)	Number of Severe Anomalies (S)
Oil ^(c)	52	3	44	3	1	1
Other	22	3	17	1	0	1
Total	74	6 ^(d)	61	4 ^(e)	1 ^(f)	2 ^(g)

Notes:

(c) Oil service is defined as natural gas liquids, oil sales, three-phase production, two-phase production (wet oil), Produced Water, and Mixed Water.

(d) All "I" locations will be prioritized based on other local and line concerns, and added as appropriate to the excavation/inspection list.

(e) All "L" locations will be re-inspected every two years.

(f) "M" location will be excavated and inspected in 2002.

(g) One "S" location was excavated and inspected in 2001. The other "S" location is in a line that is now abandoned.

3.1.e (3) Results of Crossing Digs

Nine cased pipes were excavated in 2001:

- Two of the nine pipes had moderate external damage. One of the two is now out-of-service. The other, an NGL line, was repaired with a sleeve.
- Seven of the nine pipes excavated and inspected did not require de-rating, repair, or replacement. Only minor damage was found.

For the eight cased pipes that were excavated in 2001 and remained in service, the insulation was refurbished and the pipe wrapped with Densyl tape to prevent further corrosion.



3.1.f Other Structural Concerns

Subsidence:

Existing Well Upgrade Program

- In 2001, 16 floors with riser piping supports were installed in well houses at Drill Site 2M. Well house floors are supported by the well conductor and provide table riser piping supports.
- More than thirty heat tubes were installed at 1A, 1C, 2A, 2K, 2N, 3G. Heat tubes are used to keep the ground frozen or to re-freeze the ground where it has been thawed.

New Wells & Producer to Water Injection Well Conversions

- All new wells brought on line in 2001 had heat tubes, and floors with permanent pipe supports, installed as part of their packages.
- All existing producers converted to water injection wells were also upgraded to include heat tubes and floors with permanent pipe supports.

Wind-Induced Vibration:

- As a result of the DS2X 8" MI line failure which occurred in December 2001 (described below), Kuparuk is in the process of reviewing existing pipelines to evaluate the need for vibration dampeners. The line that failed is oriented 1-degree outside the design wind direction envelope designated for Kuparuk in 1991. To date, we have identified one area that falls within the design wind direction envelope but does not have dampeners installed. We plan on covering these sections of lines in 2002. We are also reviewing the existing PAI specification to determine if it needs to be revised to include a larger degree area than is currently specified.
- Engineering performs an annual inspection of all vibration dampener (PVD) locations to verify integrity of the PVD's. This information is sent to the facilities for corrective action. Typically, corrective action consists of replacement of worn elastomers and reinstallation of PVD weights.

3.1.g Corrosion and Structural-Related Spills/Incidents

- 1HBWI External Corrosion Water Injection Line Leak – 4/15/01 – The 10-inch injection line serving drill sites 1H and 1B failed due to external corrosion at a weld pack in a cased road crossing, spilling 92,000 gallons of produced water. This road crossing had not yet been inspected using electromagnetic wave (PTI) or long-range ultrasonic (TWI) techniques. Prior to the spill, 149 above-grade weld packs on this line had been inspected with no de-rating damage found. The eight above-grade weld packs remaining to be inspected were completed in 2001 with no de-rating damage found.
- No leaks were caused by internal corrosion in 2001.
- DS 2X Miscible Injectant Line Incident – 12/31/01 – The eight-inch miscible injection line serving Drill Site 2X developed a crack at a weld, possibly due to wind-induced vibration. We are still awaiting metallurgical analysis results to rule out the possibility of a weld defect. No liquids were spilled. This line was oriented one degree outside of the susceptible wind direction for the Kuparuk field. As noted above, we are evaluating other line segments that are without PVD's and close to the susceptible wind direction to determine the need for PVD installation.
- No leaks were caused by subsidence in 2001.

Figures 8 and 9, and Figure A1 in Appendix A show the number of leaks and the volumes of leaks as a function of time. Figure 8 depicts the leaks caused by internal corrosion for the well lines. Figure 9 depicts the leaks caused by internal corrosion for the cross-country lines. Figure A1 shows the leaks caused by external corrosion for both cross-country and well lines.

3.2 Year 2002 Forecast

3.2.a Monitoring & Mitigation

- Convert the field wide corrosion inhibitor back to Cortron RU-276.
- Test new corrosion inhibitors in an effort to improve corrosion inhibition technology.
- Test sch noo-be-gone in the water injection system for one drill site.
- Develop and implement wellhead chemical injection systems for the production well lines at select drill sites.
- Decrease wet oil line corrosion exposure through increased maintenance pigging and inhibitor adjustments.

3.2.b Well Line Inspection

Based on the 2001 well line inspection programs, the following enhancements/modifications are planned for 2002:

- Inspect approximately 200 well lines at Kuparuk.
- The strategy for RTR inspection consists of performing an "initial inspection" for each line. If significant damage is found during this stage of the inspection, a "100%" inspection is then performed on the line. (Note: this is never actually 100% due to sardles, etc.). If no significant damage is found on the initial inspection of a line, the inspection crew will proceed to the next targeted line. A 25% line target was used as the "initial" footage in 2001. The plan for the 2002 inspection program is to maintain the same percentage of the initial target area.

3.2.c Cross-Country Line Inspection

Based on the 2001 cross-country line inspection programs, the following enhancements/modifications are planned for 2002:

- Maintain an equivalent level of RTR inspection as in 2001.
- Continue to implement the risk-ranked Elbow Inspection Program that increases the effectiveness of the produced crude (three-phase) cross-country line inspection program. The purpose of this program is to identify higher-risk areas on a given line, taking into account flowing conditions and pipeline geometries, so that more effective inspection schedules can be established.
- Evaluate the possibility of smart pigging cross-country water injection lines larger than 8" outside diameter.

3.2.d External (Weld-Pack) Program

- Inspect approximately 17% of well line weld packs (approximately 4,000 weld packs). All well line weld packs will be inspected by YE 2005.
- Inspect 20% of the of CC On-Pad weld packs (approximately 1,780 weld packs). All CC On-Pad weld packs will be inspected by YE 2004.



3.2.e Below Grade Piping Program

- Visually inspect all of the cased lines. The appropriate PAI field department will be notified of any corrective actions that need to be taken early enough to complete clean out and re-inspection during the summer.
- Complete the first-pass inspection of the remaining priority 1 cased lines using PTI and/or TWI techniques. There are approximately 150 cased lines that will require inspection in 2002. Based on the results from TWI and PTI, certain lines will be excavated.
- Continue to work with PTI/TWI and Phillips R&D to refine inspection data reduction and interpretation.

3.2.f Other

- Complete enhancements to the Kuparuk Corrosion Database.
- Continue to review existing Kuparuk pipeline locations to assure correct placement of WIV dampeners.
- Continue Alpine piping layout and piping information database development.
- Continue to evaluate, and prioritize subsidence mitigation efforts at the drill sites.
- Continue to evaluate snow fences to minimize snow accumulation on well lines.



APPENDIX A

Table A1. Three-phase Production Cross-Country Lines with corrosion rates that exceeded targets and the action that was taken.

<u>Common Line</u>	<u>Date</u>	<u>Coupon Grade</u>	<u>Probe Rate</u>	<u>Inspection</u>	<u>Insp Incr</u>	<u>Action Taken</u>
1-2Z1QGPO	06/18/01	A	<0.5 mpy		yes	Raised target inhibition
1-2Z1QPO	11/12/01	NA	NA		yes	Raised target inhibition
1APO	11/12/01	A	<0.5 mpy		yes	Raised target inhibition
1BPO	11/06/01	D	>0.5 mpy			Raised target inhibition
1CPO	11/06/01	D	<0.5 mpy			Initiated inhibition 12/01
1GPO	07/01/01	C	>0.5 mpy	yes	yes	Raised effective inhibitor
1L10PO	11/05/01	D	<0.5 mpy		yes	Raised target inhibition
1QPO	11/05/01	C	<0.5 mpy			Raised target inhibition
1RPO	Jan, July, Nov	F, D	> 1 mpy	yes	yes	Raised target inhibition
1YPO	11/02/01	A	<0.5 mpy		yes	Raised target inhibition
1YRPO	11/15/01	A	<0.5 mpy		yes	Raised target inhibition
24" WO at 1Q	Feb, June	D, C	> 1 mpy			Raised target inhibition then line taken out of service
2HPO	11/16/01	B	<0.5 mpy		yes	Raised target inhibition
2KPO	11/03/01	D	<0.5 mpy			Raised target inhibition
2TAMKHPO	11/10/01	A	<0.5 mpy		yes	Raised target inhibition
2TPO	11/03/01	D	>0.5 mpy			Raised target inhibition
2UPO	02/07/01	A	<0.5 mpy		yes	Raised target inhibition
3CPO	11/02/01	D	<0.5 mpy			Raised target inhibition
3GFPO	07/01/01	C	>0.5 mpy	no		Raised target inhibition
3GPO	11/01/01	C	<0.5 mpy			Raised target inhibition
3HPO	Aug, Nov	D, F	<0.5 mpy	yes		Raised target inhibition
3M	08/13/01	D	<0.5 mpy	no		Raised effective inhibitor
3MPO	11/01/01	C	<0.5 mpy			Raised target inhibition
3OPO	07/01/01	A	>0.5 mpy			Raised target inhibition
3RPO	11/02/01	C	<0.5 mpy			Raised target inhibition
3RQOPO	07/01/01	D	>0.5 mpy	yes	yes	Raised target inhibition
XCL/WO at CPF1 w. of flare pit	11/05/01	D	<0.5 mpy			Raised target inhibition
XCL/WO at CPF2	May, Nov	F, C	<0.5 mpy			Raised target inhibition




Figure A1. Leaks, saves, number of weld packs inspected with TRT, and volumes of leaks as a function of time.

Note: The leak in 2001 due to external corrosion was located in a weld pack in a below-grade piping segment, and as such, would not have been detected by the TRT inspection program. The location had not yet received PTI/TWI inspection.



APPENDIX B Glossary

Equipment Classification:

- **Well Line** – Pipe from the wellhead to the Drill Site manifold. For production wells, a well line handles the flow from a single well prior to commingling with fluids from other wells and transportation to the Central Processing Facility. For water injection wells, a well line handles the water flow going from a common manifold to a single wellhead.
- **Cross-Country Line** – Pipe from the Drill Site manifold to the Central Processing Facility (CPF).
- **Below-Grade Location** – That portion of a single pipeline, which crosses underneath a road or other earthen feature at a single location. The linear extent of the location consists of the length of pipeline between casing ends.

Service Definitions:

- **Three-phase Production** – Basic reservoir fluids (oil, water, and gas) produced from down hole through to the CPF. Typically sees changes in temperature and pressure only from reservoir changes and are essentially un-separated.
- **Seawater (SW)** – Water from the Beaufort Sea that has been treated at the Seawater Treatment Plant (STP). Note that seawater treatment at the Kuparuk STP consists of filtration, oxygen stripping using produced gas, and biociding.
- **Produced Water (PW)** – The water separated at the CPF from three-phase production.
- **Mixed Water (MW)** – Produced water and seawater that have been commingled.
- **Gas** – Generic term for the different gas systems that transport dry (no liquids) gas between facilities. Includes fuel gas, artificial lift gas, and miscible injectant.
- **Produced Oil** – The liquid hydrocarbon separated at the CPF from three-phase production.

2002



**Greater Kuparuk Area (GKA)
Alpine Field
Corrosion Programs Overview**

April 7, 2003

*Commitment to Corrosion Monitoring
3rd Annual Report to the Alaska Department of Environmental Conservation*

Prepared by
ConocoPhillips Corrosion Team

Table of Contents

1.0 Overview

2.0 Significant Changes to Corrosion Programs

3.0 Program Status Summary

3.1 Year 2002 Overview

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other Structural Concerns
- g. Spills/Incidents

3.2 Year 2003 Forecast

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other

Appendix A Corrosion Monitoring Exception Data and External Corrosion Inspection/Leak/Save Results

Appendix B Glossary of Terms used in this Report

1.0 OVERVIEW

There are over \$4MMM in capital assets in the Greater Kuparuk Area (GKA). Over the past few years, the corrosivity of the produced fluids at Kuparuk has increased to a level that has the potential to cause internal corrosion damage to the facilities. The corrosivity is increasing as water production and H₂S levels increase. External corrosion has also become a potential problem on aging pipeline systems. Effective management of corrosion at Kuparuk is critical to maintain environmental and facility integrity, reduce field operating costs, and to extend the life of the field infrastructure to meet future needs.

Alpine is ConocoPhillips' newest development and the largest onshore oil field discovered in North America in the past decade. Alpine has a gross processing capacity of 100,000 BOPD. The Alpine development produces from a pad area of 97 acres, and has 2 Drill Sites. The corrosion management system used at Kuparuk is also being applied to the new Alpine field.

The purpose of this 3rd Annual Report is to communicate the details of the individual programs that implement the ConocoPhillips Alaska Corrosion Strategy. In addition to the requirements of the North Slope Charter Agreement between ConocoPhillips Alaska, Inc., BP Exploration (Alaska), and the Alaska Department of Environmental Conservation, previous reporting requirements pertaining to the Below Grade Piping Program will be incorporated into this and future North Slope Charter Corrosion Reports.

Because of the large amount of data from corrosion monitoring and corrosion inspections, Appendix A has been added. Appendix A contains corrosion coupon exception data and external corrosion inspection and leak/save historical results.

A glossary of terms used in this report is included as Appendix B.

2.0 SIGNIFICANT ENHANCEMENTS TO CORROSION PROGRAMS

- Developed a corrosion inhibitor-screening lab in the Bartlesville technology center. In doing so we established our lab qualification testing protocols for use of Rotating Cylinder Autoclave (RCA), Interfacial Tension measurements (IFT) and Total Organic Carbon (TOC) analysis. In addition we established a method for evaluation of lab data generated during testing using statistics, allowing us to better rank performance between inhibitors for selection to actual field-testing.
- Started Corrosion Inhibitor injection at Alpine CD1 Drill Site Cross Country Line.
- Initiated a Turbulent Flow Survey (TFS) on cross-country three-phase oil lines. This program is designed to schedule fittings, such as elbows and tees, for recurring inspection based on flow characteristics, which may cause velocity assisted corrosion damage. The TFS supplements our RTR inspection program, which is designed to find internal damage in straight runs of pipe.
- Implemented use of Intrinsically safe UT machine.
- Initiated the CUI Buffer Spike test on 76 test locations during summer of 2002.

3.0 Program Status Summary

3.1 Year 2002 Overview

3.1.a Monitoring & Mitigation

Monitoring Kuparuk:

Average general and pitting coupon corrosion rate data for Year 2002 are presented in Tables 1 and 2.

Table 1. Average general corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average General Corrosion Rate, mpy (target=<3)	Number of Lines with Conformant General Corrosion Rates	Percent of Lines with Conformant General Corrosion Rates
Three-phase Production Cross-Country Lines	60	0.03	60	100
Seawater Cross-Country Lines	2	2.0	1	50
Mixed Water Injection Cross-Country Lines	22	0.6	21	95
Production Well Flow Lines	437	0.2	433	99
Mixed Water Injection Well Flow Lines	549	0.4	527	96

Table 2. Average pitting corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average Pitting Corrosion Rate, mpy (target=<10)	Number of Lines with Conformant Pitting Corrosion Rates	Percent of Lines with Conformant Pitting Corrosion Rates
Three-phase Production Cross-Country Lines	60	4.3	50	83
Seawater Cross-Country Lines	2	2.3	2	100
Mixed Water Injection Cross-Country Lines	22	1.9	14	64 ^a
Production Well Flow Lines	437	1.7	417	95
Mixed Water Injection Well Flow Lines	549	6.9	412	75

Notes:

a See graph and discussion on page 8 of this report.

Monitoring Alpine:

Average general and pitting coupon corrosion rate data for Year 2002 are presented in Tables 3 and 4.

Table 3. Average general corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average General Corrosion Rate, mpy (target=<3)	Number of Lines with Conformant General Corrosion Rates	Percent of Lines with Conformant General Corrosion Rates
Three-phase Production Cross-Country Lines	1	0	1	100
Seawater Cross-Country Lines	1	0.7	1	100
Seawater Injection Cross-Country Lines	1	0	1	100
Production Well Flow Lines	17	0.3	17	100
Seawater Injection Well Flow Lines	5	0	5	100

Table 4. Average pitting corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average Pitting Corrosion Rate, mpy (target=<10)	Number of Lines with Conformant Pitting Corrosion Rates	Percent of Lines with Conformant Pitting Corrosion Rates
Three-phase Production Cross-Country Lines	1	1.0	1	100
Seawater Cross-Country Lines	1	1.0	1	100
Seawater Injection Cross-Country Lines	1	0	1	100
Production Well Flow Lines	17	0.2	17	100
Seawater Injection Well Flow Lines	5	0.2	5	100




Figure 1. Three-phase Production Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Three-phase Production Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 1 suggest that general corrosion is under control. The data presented in the Tables 1 and 2 and in Figure 1 include corrosion coupon data from the wet oil lines.

Recurring CRM inspections also support the conclusion that corrosion is under control in the three-phase production cross-country lines. In 2002, 517 corrosion-rate monitoring (CRM) inspections were conducted, with 11 minor increases found (i.e. less than 3% of total CRM inspections resulted in an increase). Other internal inspection data also support the CRM data conclusions and are discussed in section 3.1.c, below.

Where corrosion rates exceeded targets, corrosion inhibitor concentrations were increased and/or the amount of inspection was increased. In 2002, coupon or probe corrosion rates exceeded targets on 10 lines and corrosion inhibitor concentrations were increased on all 10 of these lines. In 2002, inspection results indicated minor corrosion had occurred on 7 lines that did not have coupons or probes that exceeded the target corrosion rates; corrosion inhibitor concentrations were increased in all 7 of these lines. A complete listing of the 20 lines with corrosion rates that exceeded targets or where inspection indicated increase damage, is given Table A.1 of Appendix A.

In 2002, of the three wet oil lines only the 12" CPF2 Wet Oil Line showed any significant coupon corrosion rate; the corrosion inhibitor concentration was increased on this line.




Figure 2. Seawater Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Sea Water Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 2 above, shows the average corrosion rates for the sea water cross-country line coupons remained under thresholds in 2002. UT inspections were conducted in the area of the coupons with the high general corrosion rates and no increases to existing minor damage were found. An ER probe has been installed in the same area with no appreciable corrosion rate noted.




Figure 3. Water Injection Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Mixed Water Injection Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 3 show that average general corrosion rates are below the threshold, but that pitting rates for the field are above the threshold. Closer analysis of the data shows that the average pitting rate excluding CPF2 locations is well under the threshold. Recent inspection data from the CPF2 lines show some damage on three lines. This information, along with coupon results, was used to prioritize 2003 inspection efforts. RTR inspection work for 2003 will target 15,000 feet of cross-country water injection lines.




Figure 4. Three-phase Production Well Line Coupons – general and pitting corrosion rates as a function of time.

Three-phase Production and Mixed Water Injection Well Flow Lines: While the monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figures 4 and 5 suggest that corrosion rates are below targets, inspection data indicates that higher rates are actually being experienced. The well line inspection data are discussed in section 3.1.b below, and are a good example of why monitoring data alone cannot be relied upon to characterize corrosion in a given system.




Figure 5. Water Injection Well Line Coupons – general and pitting corrosion rates as a function of time.

Mitigation:

In first quarter 2002, the field was converted from Cortron 2000-25 to Cortron RU-276 based on poor performance of the 2000-25. One new inhibitor VX6789 was tested at DS1R; the test yielded good monitoring data, however the inhibitor did not out-perform the incumbent inhibitor.




Figure 6. Field-wide Corrosion Inhibitor Use – actual amount of corrosion inhibitor used per day, recommended amount of corrosion inhibitor used per day, and the percent difference between the actual and the recommended amounts.

For the Kuparuk field, Figure 6 shows the actual number of gallons of corrosion inhibitor pumped per day, the recommended number of gallons of corrosion inhibitor per day, and the percent difference between the two. The difference fluctuated around zero percent deviation from the recommended amount of corrosion inhibitor; the average deviation for the year was 0.9%. The extreme variation seen in the November data was caused by the production upsets associated with the earthquake prodrations.

The metrics for the mitigation program are described in the inhibitor feedback flow chart, Figure 7 below, the monitoring data table in Appendix "A", and discussions above.

Kuparuk Inhibitor Feedback System




Figure 7. Corrosion Inhibitor Feedback System.

3.1.b Well Line Inspection

As indicated in Figure 8 below, repair recommendations were initiated on 17 lines (8 injection, 9 production) in 2002 because of internal corrosion damage. The two leaks were on production lines. Repairs typically consist of either sleeving or replacing the de-rated section of line. The graph indicates a decrease in inspection footage from 2001 to 2002. This was the first year we encountered well lines with obstructions that did not allow efficient use of the RTR crawler. As a result, these lines required manual RT as the primary inspection method. We met our primary 2002 goal of inspecting all well lines with a 0.312" nominal pipe wall thickness.




Figure 8. Summary of Well Line Internal Corrosion Inspections – RT footage, leaks, and saves as a function of time.

The 2002 results from the RTR surveys, manual RT, and manual UT are summarized in the following three tables.

- RTR of Well Lines:

Service	Feet Inspected	Number of Lines Inspected
Three-phase Production	12,411	108
Water Injection	5,881	40
Total	18,292	148

The 2002 RTR well line data indicated no new damage trends.

• Manual RT of Well Lines:

Service	Number of Lines Inspected	Number of Radiographs	Number of Repeat Radiographs	Number of Repeat Radiographs with Increases	% Of Repeat Radiographs with Increases
Three-phase Production	361	2,535	633	19	3
Water Injection	145	1,207	167	15	9
Total	506	3,742	800	34	4

The 2002 manual RT well line data indicated no new damage trends.

• Manual UT of Well Lines:

Service	Number of Lines Inspected	Number of UT Inspections	Number of Repeat UT Inspections	Number of Repeat UT Inspections with Increases	% Of Repeat UT Inspections with Increases
Three-phase Production	373	3,041	2,063	165	8
Water Injection	82	616	383	23	6
Total	455	3,657	2,446	188	8

The 2002 manual UT well line data indicated no new damage trends.

3.1.c Cross-Country Line Inspection

As indicated in Figure 9, no (0) repair recommendations were initiated on cross-country lines because of internal corrosion damage in 2002. Inspection results in Figure 9 indicate that the corrosion mitigation programs are adequately protecting the three-phase lines and the water injection lines.




Figure 9. Summary of Cross-Country Line Internal Corrosion Inspection - RT footage, leaks, and saves as a function of time.

The 2002 results from the RTR surveys, manual RT, and manual UT are summarized in the following three tables:

- RTR of Cross Country (CC) Lines:

Service	Feet Inspected	Number of Lines Inspected
Three-phase Production	14,858	11
Water Injection	15,086	5
Total	29,944	16

The 2002 RTR CC line data indicated no new damage trends

- Manual RT of CC Lines:

Service	Number of Lines Inspected	Number of Radiographs	Number of Repeat Radiographs	Number of Repeat Radiographs with Increases	% of Repeat Radiographs with Increases
Three-phase Production	229	2,869	500	10	2
Water Injection	10	292	14	4	29
Total	239	3,161	514	14	3

The four increases in the water injection system were the first identified in this system to date. These four increases were confined to two of the ten WI lines inspected in 2002 (2EDCWI had three increases and 3GFB2WI had one increase).

It should be noted that manual RT is limited to those lines that are less than or equal to 10" outside diameter. For water injection service lines that are too large to effectively RT, Kuparuk relies on spot UT. Smart pigging is not an economical option at this time.

- Manual UT of CC lines:

Service	Number of Lines Inspected	Number of UT Inspections	Number of Repeat UT Inspections	Number of Repeat UT Inspections with Increases	% Of Repeat UT Inspections with Increases
Three-phase Production	105	933	600	18	3
Water Injection	28	112	9	1	11
Total	133	1,045	609	19	2

The one increase in the water injection system was the first identified in this system to date. The 2002 manual UT data supports the RT data (above) by reporting an increase in the 2EDCWI line.

3.1.d External (Weld-Pack) Program

Cross-Country Lines (On-Pad)

In 2002, significant progress was made towards the goal of completing the baseline inspections by the end of 2004. A total of 2,658 locations were inspected using tangential radiography (TRT), exceeding the goal for 2002 by 150% and placing the overall completion at 92%.

Of the 2,658 locations inspected in 2002, three locations were sleeved and one was repaired by pipe replacement.

Cross-Country Lines Over Tundra (Off-Pad)

The baseline inspection of these weld-packs was complete by year-end 2001. In 2002, an effort was initiated to verify weld pack locations and inspection data. No piping repairs were required as a result of this on-going effort. Several locations, previously identified as 'medium wet' were re-inspected, only 12% of these were found to have become more water saturated.

Well Lines

During 2002, 4116 well line weld packs were inspected, exceeding the goal of 4000. Corrosion was found at 3.5% of these locations, which were all stripped and refurbished. Two of the locations were repaired. An additional 220 locations, found to be heavy wet, were also stripped and refurbished.

Table 5: External Weld Pack Inspection Summary for 2002, including number of locations inspected, number of corroded locations, percentage of locations corroded, and number of locations refurbished by the type of line.

Type of Equipment	2002 Goal	Number of Locations Inspected	Number of Corroded Locations	Percentage of Locations Corroded	Number of Locations Refurbished
Cross-Country Lines (On-Pad)	1780	2658	48	1.8	223
Cross-Country Lines Over Tundra (Off-Pad)	0	1024	24	2.3	261
Well Lines	4000	4116	143	3.5	363
Total	5780	7798	215	2.76	847

The number of weld packs TRT'd, number of weld packs corroded, and the percentage of weld packs corroded for the cross-country lines over tundra, cross-country lines on-pad, and well lines are given in Figures 10, 11, and 12.




Figure 10. Summary of Weld Packs on Cross-Country Lines over Tundra (off-pad) – number of weld packs inspected, number of weld packs corroded, and percent of weld packs corroded.

Figure 10 illustrates the most-mature external corrosion inspection program of the three external corrosion programs. A review of results, obtained early in this program was initiated in 2002. A larger recur inspection program for these weld packs is scheduled to begin in 2003.




Figure 11. Summary of Weld Packs on Cross-Country Lines on Pads – number of weld packs inspected, number of weld packs corroded, and percent of weld packs corroded.

Figures 11 and 12 depict the results of the major focus of the external weld pack inspection program in 2002. The cross-country on-pad weld packs were inspected using a prioritization scheme based on the historical corroded-to-wet ratios of the over-tundra portions of the cross-country lines. The well line weld-packs were inspected using a prioritization scheme that examined the oldest, the hottest, and thinnest-walled lines first. As of year-end 2002, 92% of the cross-country on-pad weld-packs and 60% of the well line weld-packs have received their baseline TRT inspection.




Figure 12. Summary of Weld Packs on Well Lines – number of weld packs inspected, number of weld packs corroded, and percent of weld packs corroded.

CUI Buffer Spike Test:

A test of "CUI Buffer Spikes" was initiated on 76 locations. The sodium phosphate salt contained in these spikes dissolves in wet insulation and raises the pH to 10. Prior to installation of these spikes, wet insulation measurements fell within a consistent 6 to 7 pH range. Corrosion of carbon steel is minimized in alkaline conditions.

3.1.e Below Grade Piping Program

In 2001, ADEC and ConocoPhillips Alaska, Inc., agreed to consolidate the Below Grade Piping Program report with the Commitment to Corrosion Monitoring Report. This section details the inventory and survey of below grade locations and the results of Specialty Testing. The plans for future inspections are given in section 3.2.e.

The Alaska Department of Environmental Conservation (ADEC) regulations under 18 AAC 75.080 apply to the Kuparuk oilfield facilities operated by ConocoPhillips Alaska, Inc. (CPAI). To meet the requirements of 18 AAC 75.080, CPAI submitted their corrosion control program for below-grade piping in early 1998. The program also included a field-wide inventory of all below-grade piping in the Kuparuk field. ADEC approved the program in written correspondence dated October 26, 1998.

3.1.e (1) Inventory and Survey of Below Grade Locations

CPAI has 416 locations of below grade "oil" piping in the GKA and Alpine oil fields. Of these locations, one is contained in an utilidor. The remaining locations are cased lines, the majority of which are either road or caribou crossings. In addition to the "oil" piping, PAI has 243 significant below grade locations with lines in other services.

Utilidor Line

Inspection Status:

The one line in an utilidor (below-grade identification number 286) was inspected in 1999 and again in 2002. The 2002 radiographic inspection showed no change in the damage identified in the 1999 inspection.

Cased Lines

Inspection Status:

The annual visual survey of all the cased lines was conducted in 2002. The purpose of the survey was to identify, rectify, and report local conditions (e.g., debris found in casings and culverts, pipe insulation in contact with soil) that require remedial action.

Results and Remedial Action:

Of all the below-grade oil lines, 43 locations were found to have pipe in direct contact with soil and/or gravel/soil or debris in the casing. All 43 were remediated in 2002.

3.1.e (2) Results of Specialty Testing

Inspection Status:

In 2002, we completed the PTI/TWI inspections on all remaining priority one locations.

Both the long-range ultrasonic system technology from The Welding Institute (TWI) and the electromagnetic wave pulse system from Profile Technologies, Inc. (PTI) were used. Testing with PTI was limited to those lines without a significant risk for internal corrosion. PTI is used to find external electromagnetic anomalies such as external corrosion, but cannot find internal corrosion. The TWI technology was applied to lines with a risk for internal corrosion. TWI was also used to evaluate any positive indications detected by PTI, since PTI finds electromagnetic anomalies and is prone to finding false positives.

In addition to using TWI's long-range ultrasonic system technology, CPAI evaluated the torsional wave inspection technique from TWI. CPAI has determined that the torsional wave technique is not superior to the TWI long-range ultrasonic system and CPAI will not use the torsional wave technique unless further improvements are made.

Results and Remedial Action:

Tables 6 and 7 show the results of the specialty testing performed by PTI and TWI, respectively.

Table 6. Results from the PTI inspections by service.

Service	Number of Cased Pipes Inspected	Inconclusive Results (I) ^(b)	Number without any Electromagnetic Anomalies (N)	Number of Electromagnetic Anomalies (E)	Number of Significant Electromagnetic Anomalies (S)
Oil ^(a)	53	3	30	10	10
Other	81	1	59	15	6
Total	134	4	89	25 ^(c)	16 ^(c)

Notes:

(a) Oil service is defined as natural gas liquids (NGL), oil sales, three-phase production, two-phase production (wet oil), Produced Water, and Mixed Water.

(b) One gas line inconclusive scheduled for TWI inspection in 2003. One NGL location excavated, with no de-rating damage found. One line was abandoned and one line was inspected with TWI.

(c) All "S" and "E" locations were inspected with TWI, except for two pipes with "E" that will be inspected with TWI in 2003. The two pipes with "E" in 2002 that were not inspected by TWI in 2002 were:

- ID #533 (3RWI) was added to the 2003 TWI inspection list.
- ID #573 (STP-to-3-SW) was added to the 2003 TWI inspection list.

Table 7. Results from the TWI inspections by service.

Service	Number of Cased Pipes Inspected	Incomplete or Inconclusive Results (I)	Number without any Significant Indications (N)	Number of Minor (Low) Anomalies (L)	Number of Moderate Anomalies (M)	Number of Severe Anomalies (S)
Oil ^(d)	27	9	14	0	2	2
Other	28	4	21	0	1	0
Total	53	13 ^(e)	35	0 ^(f)	3 ^(g)	2 ^(h)

Notes:

- (d) Oil service is defined as natural gas liquids, oil sales, three-phase production, two-phase production (wet oil), Produced Water, and Mixed Water.
- (e) "I" locations are prioritized based on other local and line concerns, and added as appropriate to the excavation/inspection list.
- (f) "L" locations are re-inspected (PTI/TWI) every two years.
- (g) "M" locations are typically evaluated, excavated, inspected and refurbished during the next excavation season. Regarding the three "M" locations found in 2002:
 - ID #159 (1YRPO) was added to the excavation list. It will be evaluated for excavation along with all other locations on the list. It does not appear this location will be excavated during the 2003 season because of the liberal "corrosion allowance" resulting from the combination of thick pipe wall (0.938") and low operating pressure.
 - ID #160(CPF1 WO) was excavated in 2002. Moderate to severe CUI was found and the damage was sleeved.
 - ID #763 (KIC fuel gas supply line) had damage reported outside the casing that was further evaluated by RT. No damage was found. The indications originated from a foamed-in-place anchor rather than from corrosion damage.
- (h) "S" locations are typically excavated inspected and refurbished during the excavation season. Regarding the two "S" locations found in 2002:
 - ID #575 (3RPO) had damage reported outside the casing that was further evaluated by RT. No damage was found. The indication originated from weld fit up rather than from corrosion damage.
 - ID #97 (1E-13 well line) was de-pressured and put on the Long Term Shut-In List.

3.1.e (3) Results of Crossing Digs

Eight cased pipes were excavated in 2002:

- Two of the eight pipes had severe to moderate damage, one internally damaged and one externally damaged. The section of line that was internally damaged was replaced. The section of line that had external damage was sleeved.
- Six of the eight pipes excavated and inspected did not require de-rating, repair, or replacement. Only minor damage was found.

For all eight cased pipes that were excavated in 2002, the insulation was refurbished and the pipe wrapped with Densyl tape to prevent further corrosion.

3.1.f Other Structural Concerns

Subsidence:

Existing Well Upgrade Program

- In 2002, 45 floors with riser piping supports were installed in well houses at Drill Sites 1A, 1D, 2T, 3F, 3O, and 3Q. Well house floors are supported by the well conductor and provide table riser piping supports.
- In 2002, 44 heat tubes were installed at Drill Sites 1C, 1D, 1R, 2K, 2N, and 2T. Heat tubes are used to keep the ground frozen or to re-freeze the ground where it has been thawed.

New Wells & Producer to Water Injection Well Conversions

- In 2002, nine new wells brought on line had heat tubes, and floors with permanent pipe supports, installed. Three new wells were installed with insulated conductors.
- In 2002, all 13 existing producers converted to water injection wells were upgraded to include heat tubes. Previously, these wells had installed conductor-supported floors.

Wind-Induced Vibration:

- As a result of the DS2X 8" MI line failure that occurred in December 2001, Kuparuk evaluated the need for vibration dampeners on existing pipelines. The line that failed is oriented one-degree outside the design wind direction envelope designated for Kuparuk in 1991. We identified six other lines that fall within the design wind direction envelope but did not have dampeners installed. One of these six lines has had tuned vibration absorbers (TVA's) installed. The design of TVA's for two of these six lines is complete and installation is scheduled. The remaining three lines at DS 3N are on the edge of the wind fan; strain gauges will be attached on all three of these lines and the movement of the lines will be monitored.
- An annual inspection of all pipeline vibration dampener (PVD) locations is conducted to verify integrity of the PVD's. This information is sent to the facilities for corrective action. Typically, corrective action consists of replacement of worn elastomers and reinstallation of PVD weights.

3.1.g Corrosion and Structural-Related Spills/Incidents

- 2A-18 Internal Corrosion Production Well Line Leak – 4/07/02 – The six-inch production line serving well 2A-18 failed because of internal corrosion just above a corrosion access fitting. Total spill volume was 1200 gallons of product (8% oil and 92% produced water) that was confined to the pad. No other locations on this line required repair. Similar locations on 283 other lines were inspected and no repairs were required because of a similar corrosion mechanism.
- 2T-13 Internal Corrosion Production Well Line Leak – 7/25/02 – The six-inch production line serving well 2T-13 failed because of internal corrosion in a straight-run section of pipe; the failure was caused by under-deposit corrosion in the low-velocity pipeline. Total spill volume was 10 gallons of product (41% oil and 59% produced water) that was confined to pad. All well lines (34) at DS 2T were inspected, with no damage found on 28 well lines. Six well lines showed damage similar to 2T-13, but no de-rating damage was found; one section of another well line, though not de-rated, has also been recommended for replacement.
- No leaks were caused by external corrosion in 2002.
- No leaks were caused by wind-induced vibration in 2002.
- No leaks were caused by subsidence in 2002.

Figures 8 and 9, and Figure A1 in Appendix A show the number of leaks and the volumes of leaks as a function of time. Figure 8 depicts the leaks caused by internal corrosion for the well lines. Figure 9 depicts the leaks caused by internal corrosion for the cross-country lines. Figure A1 shows the leaks caused by external corrosion for cross-country lines, well lines, and below-grade piping locations.

3.2 Year 2003 Forecast

3.2.a Monitoring & Mitigation

- Test new corrosion inhibitors in an effort to improve corrosion inhibition technology. Testing of Champion 2002-49a is underway in the DS1R cross-country line.
- Test schmoobee-gone in the water injection system for DS1E.
- Implement wellhead chemical injection systems for the production well lines at Drill Sites 1A, 1H, 1Y, and 2T.
- Continue analysis of the CPF2 mixed water and associated systems to determine the cause of higher corrosion rates.

3.2.b Well Line Inspection

Complete baseline inspection of all six-inch OD, 0.312" and 0.375" wall-thickness well lines that are six years of age or older.

3.2.c Cross-Country Line Inspection

The following enhancements/modifications are planned for 2003:

- RTR ~15,000 feet of cross country lines in 2003 concentrating on water injection lines.
- Complete inspection of elevation-change elbows scheduled as part of the Cross-Country Line Turbulent Flow Survey.

3.2.d External (Weld-Pack) Program

Complete evaluation of the initial CUI Buffer Spike test and determine the way forward.

Cross-country lines over tundra:

- Complete recur TRT inspections on approximately 1500 CUI locations; use results to help establish a prioritization scheme for future recurring inspection schedule and continue to monitor Denso tape protocol.
- Complete approximately 100 TRT inspections on the Tarn weld pack design established in 1997.
- Complete visual inspections of Medium Wet weld packs in saddles on large diameter sea water lines. Strip, inspect and refurbish these directly without performing TRT inspections because of the lengthy shot times involved.

For cross-country lines on-pad, inspect half of the remaining weld packs without a baseline inspection. This supports the goal of YE 2004 completion.

For well lines, inspect approximately 17% of the remaining weld packs without a baseline inspection. This supports the goal of YE 2005 completion.

3.2.e Below Grade Piping Program

- Visually inspect all of the cased lines. The appropriate PAI field department will be notified of any corrective actions that need to be taken early enough to complete clean out and re-inspection during the summer.
- Initiate recurring PTI/TWI Inspections of priority-1 cased lines.
- Complete the first-pass inspection of the remaining priority-2 cased lines using visual inspection and gas sniffing procedures as noted in our ADEC approved procedure.
- Complete excavations of five-to-nine lines in road crossing for visual inspection, refurbishment and repair, as necessary.
- Continue to work with PTI/TWI and ConocoPhillips R&D to refine inspection data reduction and interpretation.

3.2.f Other

- Continue enhancements to the Kuparuk Corrosion Database.
- Continue Alpine piping layout and piping information database development.
- Continue to evaluate, and prioritize subsidence mitigation efforts at the existing drill sites.

APPENDIX A

Table A1. Three-phase Production Cross-Country lines with corrosion rates that exceeded targets and the action that was taken.

Common Line	Coupon Grade	Probe Rate	Insp Incr	Action Taken
1-2Z1QGPO	A	<.5	yes	Target CI Rate increased
1-2ZPO	A	<.5	yes	Target CI Rate increased
1FPO	NA	NA	yes	Actual CI Rate increased
1RPO	C	<.5		Target CI Rate increased
2APO	A	0.5	yes	Target CI Rate increased
2CPO	NA	NA	yes	Target CI Rate increased
2FPO	A	<.5	yes	Target CI Rate increased
2KPO	C	<.5		Target CI Rate increased
2TAMKHPO	A	<.5	yes	Target CI Rate increased
2TPO	D	<.5		Target CI Rate increased
2UPO	A	<.5	yes	Target CI Rate increased
2WUPO	C	<.5		Target CI Rate increased
2WUVPO	F	<.5	yes	Target CI Rate increased
3CPO	D	<.5		Target CI Rate increased
3MIPO	D	<.5		Target CI Rate increased
3NPO	C	<.5		Target CI Rate increased
3RQONKPO	C	1.2		Target CI Rate increased
3RQOPO	C	<.5		Target CI Rate increased
XCL/WO at CPF2	C	<.5		Target CI Rate increased
XCL/WO to CPF1	B	NA	yes	Target CI Rate increased




Figure A1. Leaks, saves, number of weld packs inspected with TRT, and volumes of leaks as a function of time.

Note: The leak in 2001 due to external corrosion was located in a weld pack in a below-grade piping segment, and as such, would not have been detected by the TRT inspection program. The location had not yet received PTi/TWI inspection.

APPENDIX B Glossary

Equipment Classification:

- **Well Line** – Pipe from the wellhead to the Drill Site manifold. For production wells, a well line handles the flow from a single well prior to commingling with fluids from other wells and transportation to the Central Processing Facility. For water injection wells, a well line handles the water flow going from a common manifold to a single wellhead.
- **Cross-Country Line** – Pipe from the Drill Site manifold to the Central Processing Facility (CPF).
- **Below-Grade Location** – That portion of a single pipeline, which crosses underneath a road or other earthen feature at a single location. The linear extent of the location consists of the length of pipeline between casing ends.

Service Definitions:

- **Three-phase Production** – Basic reservoir fluids (oil, water, and gas) produced from down hole through to the CPF. Typically sees changes in temperature and pressure only from reservoir changes and are essentially un-separated.
- **Seawater (SW)** – Water from the Beaufort Sea that has been treated at the Seawater Treatment Plant (STP). Note that seawater treatment at the Kuparuk STP consists of filtration, oxygen stripping using produced gas, and biociding.
- **Produced Water (PW)** – The water separated at the CPF from three-phase production.
- **Mixed Water (MW)** – Produced water and seawater that have been commingled.
- **Gas** – Generic term for the different gas systems that transport dry (no liquids) gas between facilities. Includes fuel gas, artificial lift gas, and miscible Injectant.
- **Produced Oil** – The liquid hydrocarbon separated at the CPF from three-phase production.

Inspection Terminology:

- **CRM** – Corrosion rate monitoring.
- **UT** – Ultrasonic testing
- **RT** – Radiographic testing
- **RTR** – Real time radiographic testing
- **TRT** – Tangential radiographic testing
- **PTI** – Profile Technologies Inc. (Electro magnetic inspection)
- **TWI** – The Welding Institute (Long range UT)
- **KDR** – Known damage recur inspection

2003



**Greater Kuparuk Area (GKA)
Alpine Field
Corrosion Programs Overview**

April 1, 2004

Commitment to Corrosion Monitoring
4th Annual Report to the Alaska Department of Environmental Conservation

Prepared by
ConocoPhillips Corrosion Team

Table of Contents

1.0 Overview

2.0 Significant Enhancements to Corrosion Programs

3.0 Program Status Summary

3.1 Year 2003 Overview

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other Structural Concerns
- g. Spills/Incidents

3.2 Year 2004 Forecast

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other

Appendix A Corrosion Monitoring Exception Data and External Corrosion Inspection/Leak/Save Results

Appendix B Glossary of Terms used in this Report

1.0 OVERVIEW

There are over \$4 Billion in capital assets in the Greater Kuparuk Area (GKA). The internal corrosion potential in Kuparuk lines continues to rise as water production and H₂S levels increase. Additionally, an external corrosion potential exist where moisture penetrates and is trapped in insulation. Effective management of corrosion at Kuparuk is critical to maintain environmental and facility integrity, reduce field operating costs, and to extend the life of the field infrastructure to meet future needs.

Alpine is ConocoPhillips' newest development and its largest onshore oil field discovered in North America in the past decade. Alpine has a nominal processing capacity of 100,000 BOPD. The Alpine development produces from a pad area of 97 acres, and has two Drill Sites; additional satellite drill sites are planned. The corrosion management system used at Kuparuk is being applied to the Alpine field.

The purpose of this 4th Annual Report is to communicate the details of the individual programs that implement the ConocoPhillips Alaska Corrosion Strategy. In addition to the requirements of the North Slope Charter Agreement between ConocoPhillips Alaska, Inc., BP Exploration (Alaska), and the Alaska Department of Environmental Conservation, previous reporting requirements pertaining to the Below Grade Piping Program will be incorporated into this and future North Slope Charter Corrosion Reports.

Because of the large amount of data from corrosion monitoring and corrosion inspections, corrosion coupon exception data and external corrosion inspection and leak/save historical results are contained in Appendix A.

A glossary of terms used in this report is included as Appendix B.

2.0 SIGNIFICANT ENHANCEMENTS TO CORROSION PROGRAMS

- Completed an initial Turbulent Flow Survey (TFS) on cross-country three-phase oil lines. This program is designed to schedule fittings, such as elbows and tees, for recurring inspection based on flow characteristics, which may cause velocity assisted corrosion damage. The TFS supplements our RTR inspection program, which is designed to find internal damage in straight runs of pipe.
- Completed a baseline inspection of all well lines and cross-country lines requiring inspection.
- Wellhead corrosion inhibition design specifications have been finalized and new installations are in progress.
- Enhancements to our Bartlesville corrosion inhibitor lab screening and installation of additional monitoring points have allowed for field-testing of four new corrosion inhibitors in 2003.

3.0 Program Status Summary

3.1 Year 2003 Overview

3.1.a Monitoring & Mitigation

Monitoring Kuparuk:

Average general and pitting coupon corrosion rate data for Year 2003 are presented in Tables 1 and 2.

Table 1. Average general corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average General Corrosion Rate, mpy (target=<3)	Number of Lines with Conformant General Corrosion Rates	Percent of Lines with Conformant General Corrosion Rates
Three-phase Production Cross-Country Lines	62	0.03	62	100
Seawater Cross-Country Lines	2	3.1	1	50
Mixed Water Injection Cross-Country Lines	22	0.4	22	100
Production Well Flow Lines	451	0.3	446	99
Mixed Water Injection Well Flow Lines	551	0.6	521	95

Table 2. Average pitting corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average Pitting Corrosion Rate, mpy (target=<10)	Number of Lines with Conformant Pitting Corrosion Rates	Percent of Lines with Conformant Pitting Corrosion Rates
Three-phase Production Cross-Country Lines	62	4.5	54	87
Seawater Cross-Country Lines	2	3.3	2	100
Mixed Water Injection Cross-Country Lines	22	1.9	12	55 ^a
Production Well Flow Lines	451	1.5	433	96
Mixed Water Injection Well Flow Lines	551	8.9	376	68

Notes:

- a See graph and discussion on page 8 of this report.

Monitoring Alpine:

Average general and pitting coupon corrosion rate data for Year 2003 are presented in Tables 3 and 4.

Table 3. Average general corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average General Corrosion Rate, mpy (target=<3)	Number of Lines with Conformant General Corrosion Rates	Percent of Lines with Conformant General Corrosion Rates
Three-phase Production Cross-Country Lines	1	0	1	100
Seawater Cross-Country Lines	1	0.4	1	100
Seawater Injection Cross-Country Lines	0*			
Production Well Flow Lines	29	0.1	29	100
Seawater Injection Well Flow Lines	8	0	8	100

Table 4. Average pitting corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average Pitting Corrosion Rate, mpy (target=<10)	Number of Lines with Conformant Pitting Corrosion Rates	Percent of Lines with Conformant Pitting Corrosion Rates
Three-phase Production Cross-Country Lines	1	1.0	1	100
Seawater Cross-Country Lines	1	0.7	1	100
Seawater Injection Cross-Country Lines	0*			
Production Well Flow Lines	29	0.1	29	100
Seawater Injection Well Flow Lines	8	0.1	8	100

* NOTE: This coupon location is currently not accessible because of a new piping obstruction.




Figure 1. Three-phase Production Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Three-phase Production Cross-Country Lines: The monitoring data summarized in Kugaruk Tables 1 and 2 and presented in Figure 1 suggest that general corrosion is under control. The data presented in the Tables 1 and 2 and in Figure 1 include corrosion coupon data from the wet oil lines starting at CPF3 and going to CPF1 and CPF2.

Recurring CRM inspections also support the conclusion that corrosion is under control in the three-phase production cross-country lines. In 2003, 584 corrosion-rate monitoring (CRM) inspections were conducted, with five minor increases found (i.e. less than 1% of total CRM inspections resulted in an increase). Other internal inspection data also support the CRM data conclusions and are discussed in section 3.1 c, below.

Where corrosion rates exceeded targets, corrosion inhibitor concentrations were increased and/or the amount of inspection was increased. In 2003, coupon or probe corrosion rates exceeded targets on 17 lines and action was taken on all 17 of these lines. In 2003, inspection results indicated minor corrosion had occurred on five lines; corrosion inhibitor concentrations were increased in all five of these lines. A complete listing of the 22 lines with coupon/probe corrosion rates that exceeded targets or where inspection indicated increased damage, is given Table A1 of Appendix A.

In 2003, the 16-inch CPF3-to-CPF1 Wet Oil Line showed coupon pitting corrosion rates above the threshold of 10 mpy; actual inhibitor concentration was verified and adjusted based on coupon results. Additionally, later in the year this line experienced a lower water cut and the corrosion inhibitor concentration was adjusted.




Figure 2. Seawater Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Sea Water Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 2 above, shows the average corrosion rates for the sea water cross-country line coupons remained under thresholds in 2003. The coupon location on the 30" STP discharge line showed general corrosion rates above threshold in 2003. This is likely due to short term increased dissolved oxygen levels, the origin of which is under investigation.




Figure 3. Water Injection Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Mixed Water Injection Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 3 show that average general corrosion rates are below the threshold, but that pitting rates for the field are above the threshold. Closer analysis of the data shows that the average pitting rate excluding CPF2 locations is well under the threshold. Recent inspection data from the CPF2 lines show some damage on three lines. This information, along with coupon results, was used to prioritize 2003 inspection efforts. RTR inspection performed in 2003 included 23,099 feet on 28 cross-country water injection lines. A review of the CPF biocide programs has been conducted and new treatment procedures are in place.




Figure 4. Three-phase Production Well Line Coupons – general and pitting corrosion rates as a function of time.

Three-phase Production Well Flow Lines: While the monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figures 4 and 5 suggest that corrosion rates are below targets, inspection data indicate that higher corrosion rates have been experienced historically. The well line inspection data are discussed in section 3.1.b below, and are a good example of why monitoring data alone cannot be relied upon to characterize corrosion in a given system. For three-phase production, coupons monitor free flowing fluid and have not shown the predominant, under-deposit corrosion mechanism.




Figure 5. Water Injection Well Line Coupons – general and pitting corrosion rates as a function of time.

Water Injection Well Flow Lines: There is an increasing trend in the coupon pitting rates. As discussed in section 3.1.b below, the well line inspection data on water injectors show that there are a significant (22) and an increasing number of corrosion related repairs.

Mitigation:




Figure 6. Field-wide Corrosion Inhibitor Use.

For the Kuparuk field, Figure 6 shows the actual number of gallons of corrosion inhibitor pumped per day, the recommended number of gallons of corrosion inhibitor per day, and the percent difference between the two. The difference fluctuated around zero percent deviation from the recommended amount of corrosion inhibitor; the average deviation for the year was -1.0%. The larger variation seen in the December 2003 data was caused by the extreme weather that caused delays in routine pump rate checks and refilling of chemical tanks.

The mitigation program is described in the inhibitor feedback flow chart, Figure 7 below. Reasons for changes to target inhibitor concentrations are given in Appendix A.

Kuparuk Inhibitor Feedback System




Figure 7. Corrosion Inhibitor Feedback System.

3.1.b Well Line Inspection

As indicated in Figure 8 below, repair recommendations were initiated on 24 lines (22 injection, 2 production) in 2003 because of internal corrosion damage. Repairs typically consist of either installing a sleeve or replacing the de-rated section of line. We met our primary 2003 goal of completing the inspection of all well lines requiring baseline inspection.




Figure 8. Summary of Well Line Internal Corrosion Inspections – RT footage, leaks, and saves as a function of time.

The 2003 results from the RTR surveys, manual RT, and manual UT are summarized in the following three tables.

- RTR of Well Lines:

Service	Feet Inspected	Number of Lines Inspected
Three-phase Production	8,783	104
Water Injection	6,960	76
Total	15,743	180

The 2003 RTR well line data indicated no new damage trends.

- Manual RT of Well Lines:

Service	Number of Lines Inspected	Number of Radiographs	Number of Repeat Radiographs	Number of Repeat Radiographs with Increases	% Of Repeat Radiographs with Increases
Three-phase Production	344	2,137	856	24	3
Water Injection	208	1,715	334	26	8
Total	552	3852	1,190	50	4

The 2003 manual RT well line data indicated no new damage trends.

• Manual UT of Well Lines:

Service	Number of Lines Inspected	Number of UT Inspections	Number of Repeat UT Inspections	Number of Repeat UT Inspections with Increases	% Of Repeat UT Inspections with Increases
Three-phase Production	201	1600	1,374	92	7
Water Injection	92	784	553	40	7
Total	493	2,384	1,927	132	7

The 2003 manual UT well line data indicated no new damage trends.

3.1.c Cross-Country Line Inspection

As indicated in Figure 9, nine repair recommendations were initiated on cross-country lines because of internal corrosion damage in 2003. The corrosion mechanisms were deadleg corrosion (five repairs), under deposit corrosion (three repairs) and weld attack on a flowing line (one repair). Because of large increase in repairs we will increase our inspection effort on deadlegs in 2004.




Figure 9. Summary of Cross-Country Line Internal Corrosion Inspections – RT footage, leaks, and saves as a function of time.



The 2003 results from the RTR surveys, manual RT, and manual UT are summarized in the following three tables:

• **RTR of Cross Country (CC) Lines:**

Service	Feet Inspected	Number of Lines Inspected
Three-phase Production	20,447	31
Water Injection	23,099	28
Total	43,546	59

The 2003 RTR CC line data indicated no new damage trends

• **Manual RT of CC Lines:**

Service	Number of Lines Inspected	Number of Radiographs	Number of Repeat Radiographs	Number of Repeat Radiographs with Increases	% of Repeat Radiographs with Increases
Three-phase Production	217	2,660	581	10	2
Water Injection	17	563	18	1	6
Total	234	3,223	599	11	2

It should be noted that effective manual RT is limited to those lines water that are less than approximately 10" to 12" outside diameter. The maximum diameter for RT of three-phase production lines depends on the percentage of gas. For water injection service lines that are too large to effectively RT, Kugaruk relies on spot UT. Smart pigging is not an economical option at this time.

• **Manual UT of CC lines:**

Service	Number of Lines Inspected	Number of UT Inspections	Number of Repeat UT Inspections	Number of Repeat UT Inspections with Increases	% Of Repeat UT Inspections with Increases
Three-phase Production	104	660	789	22	3
Water Injection	30	128	21	8	38
Total	134	2,788	810	30	8

The eight increases on WI lines in 2003 represents a significant jump from previous years. The jump was caused by our increased inspection on one significantly damaged line (2EDCWI). Six of the eight increases were on this line. As a result of our 2003 inspection efforts, 2EDCWI received extensive repairs.

3.1.d External (Weld-Pack) Program

Cross-Country Lines (On-Pad)

In 2003, significant progress was made towards the goal of completing the baseline inspections by the end of 2004. A total of 580 locations were inspected using tangential radiography (TRT), significantly exceeding the goal of 343 for 2003 and placing the overall completion at 96%.

Of the 580 locations inspected in 2003, none of the locations needed repair while 122 locations were refurbished.



Cross-Country Lines Over Tundra (Off-Pad)

The baseline inspection of these weld-packs was believed complete by year-end 2001. However, in 2003 a walk down verification survey revealed that several corrosion-under-insulation (CUI) locations had been missed during the initial layout. In 2003, 2712 CUI locations were inspected. These numbers include inspections of weld packs that had been inspected previously, as well as weld packs where documentation of a previous inspection could not be verified (approximately 1000 locations). No piping repairs were required as a result of this on-going effort and 466 locations were refurbished. Although the goal in 2003 was to inspect 2746 CUI locations, severe weather in mid- to late-December delayed our ATRT inspection work and only 2712 were completed. During the first four days of 2004, we completed ATRT inspections of 119 CUI locations, bringing the total up to 2831. So, for all intents and purposes, the 2003 goal was surpassed.

Additionally, 100 of the new style weld packs used on the Tarr Line were TRT inspected to see how they are holding up. None of the weld packs inspected showed any ingress of water or presence of corrosion, indicating good performance thus far.

Well Lines

During 2003, 2728 well line weld packs were inspected, exceeding the goal of 2500. Corrosion was found at 1.9% of these locations. Also during 2003, 105 well line CUI locations were refurbished.

Table 5: External Weld Pack Inspection Summary for 2003.

Type of Equipment	2003 Goal	Number of Locations Inspected	Number of Corroded Locations	Percentage of Locations Corroded	Number of Locations Refurbished
Cross-Country Lines (On-Pad)	34	580	26	4.5	122
Cross-Country Lines Over Tundra (Off-Pad)	2746	2712	97	3.6	466
Well Lines	2500	2728	53	1.9	105
Total	5589	6020	176	2.92	693

The number of weld packs TRT'd, number of weld packs corroded, and the percentage of weld packs corroded for the cross-country lines over tundra, cross-country lines on-pad, and well lines are given in Figures 10, 11, and 12.




Figure 10. Summary of Weld Packs on Cross-Country Lines over Tundra (off-pad).

Figure 10 illustrates the most-complete external corrosion inspection program of the three external corrosion programs. 2002 and 2003 values include re-inspections and clean-up of locations missed or not properly documented during the original base line effort.




Figure 11. Summary of Weld Packs on Cross-Country Lines on Pads.

Figures 11 and 12 depict the results of the major focus of the external weld pack inspection program in 2003. The cross-country on-pad program is nearing completion and all baseline inspections should be complete by year-end 2004. The well line weld-packs were inspected using a prioritization scheme that examined the oldest, the hottest, and the thinnest-walled lines first. As of year-end 2003, 96% of the cross-country on-pad weld-packs and 91% of the well line weld-packs have received their baseline TRT inspections.




Figure 12. Summary of Weld Packs on Well Lines.

In 2002, a test of "CUI Buffer Spikes" was initiated on 76 locations. The sodium phosphate salt contained in these spikes dissolves in wet insulation and raises the pH to 10. Prior to installation of these spikes, wet insulation measurements fell within a consistent 6 to 7 pH range. Corrosion of carbon steel is minimized in alkaline conditions. During 2003, each of these locations was monitored for pH increase. The 2003 follow-up inspections showed that the pH did rise in the wet areas of the weld pack. TRT inspection of these areas is scheduled for 2004.

3.1.e Below Grade Piping Program

This section details the inventory and survey of below grade locations and the results of Specialty Testing. The plans for future inspections are given in section 3.2.e.

The Alaska Department of Environmental Conservation (ADEC) regulations under 18 AAC 75.080 apply to the Kuparuk oilfield facilities operated by ConocoPhillips Alaska, Inc. (CPAI). To meet the requirements of 18 AAC 75.080, CPAI submitted their corrosion control program for below-grade piping in early 1998. The program also included a field-wide inventory of all below-grade piping in the Kuparuk field. ADEC approved the program in written correspondence dated October 26, 1998.

3.1.e (1) Inventory and Survey of Below Grade Locations

CPAI has 416 locations of below grade (BG) "oil" piping in the GKA and Alpine oil fields. Of these locations, one is contained in an utilidor. The remaining locations are cased lines, the majority of which are either road or caribou crossings. In addition to the "oil" piping, CPAI has 243 significant below grade locations with lines in other services.

Utilidor Line

Inspection Status:

The line in the utilidor (Oily Waste Injection Line, BG ID #286) was inspected in 1999 and again in 2002. The 2002 radiographic inspection showed no change in the damage identified in the 1999 inspection. This line is evaluated for re-inspection every two years.

Cased Lines

Inspection Status:

The annual visual survey of all the cased lines was conducted in 2003. The purpose of the survey was to identify, rectify, and report local conditions (e.g., debris found in casings and culverts, pipe insulation in contact with soil) that require remedial action.

Results and Remedial Action:

Of all the below-grade lines, 45 locations were found to have pipe in direct contact with soil and/or gravel/soil or debris in the casing. All 45 locations were remediated in 2003.

3.1.e (2) Results of Specialty Testing

Inspection Status:

In 2003, we completed the PTI/TWI inspections on 82 priority one locations. This was the first year of our recurring inspection program where each priority one pipe will be inspected at a maximum ten-year interval.

Both the long-range ultrasonic system technology from The Welding Institute (TWI) and the electromagnetic wave pulse system from Profile Technologies, Inc. (PTI) were used. Testing with PTI was limited to those lines without a significant risk for internal corrosion. PTI is used to find external electromagnetic anomalies such as external corrosion, but cannot find internal corrosion. The TWI technology was applied to lines with a risk for internal corrosion. TWI was also used to evaluate any positive indications detected by PTI, since PTI finds electromagnetic anomalies and is prone to finding false positives.

In addition to using TWI's long-range ultrasonic system technology, CPAI evaluated the torsional (guided) wave inspection technique from B&E. CPAI has determined that the torsional wave technique offered by B&E is not superior to the TWI long-range ultrasonic system and CPAI will not use the torsional wave technique unless further improvements are made.

Results and Remedial Action:

Tables 6 and 7 show the results of the specialty testing performed by PTI and TWI, respectively.

Table 6. Results from the PTI inspections by service.

Service	Number of Cased Pipes Inspected	Inconclusive Results (I)	Number without any Electromagnetic Anomalies (N)	Number of Electromagnetic Anomalies (E)	Number of Significant Electromagnetic Anomalies (S)
Oil ^(a)	30	0	18	11	1
Other	3	0	1	2	0
Total	33	0	19	13 ^(b)	1 ^(b)

Notes:

- (a) Oil service is defined as natural gas liquids (NGL), oil sales, three-phase production, two-phase production (wet oil), Produced Water, and Mixed Water.
- (b) All "S" and "E" locations were inspected with TWI. The two "E" pipes remaining from 2002 were inspected with TWI in 2003.

Table 7. Results from the TWI inspections by service.

Service	Number of Cased Pipes Inspected	Incomplete or Inconclusive Results (I)	Number without any Significant Indications (N)	Number of Minor (Low) Anomalies (L)	Number of Minor to Moderate and Moderate Anomalies (M)	Number of Moderate to Severe and Severe Anomalies (S)
Oil ^(c)	62	8	28	13	8	5
Other	04	0	1	2	0	1
Total	66	8 ^(d)	29	15 ^(e)	8 ^(f)	6 ^(g)

Notes:

- (c) Oil service is defined as natural gas liquids, oil sales, three-phase production, two-phase production (wet oil), Produced Water, and Mixed Water.
- (d) "I" locations are prioritized based on other local and line concerns, and added as appropriate to the excavation/inspection list.
- (e) "L" locations are re-inspected (with PTI and/or TWI) every two years.
- (f) "M" locations are added to the excavation candidate list and evaluated for excavation, further inspection, refurbishment and repair during subsequent excavation seasons. The eight "M" pipes found by TWI in 2003 are listed here:
 - ID #71 (14" 1CPO)
 - ID #78 (14" 1EPO)
 - ID #83 (14" 1EPO)
 - ID #231 (24" 1YPO)
 - ID #327 (14" 2DPO)
 - ID #438 (8" 2FWI)
 - ID #458 (12" 2FPO)
 - ID #533 (8" 3R SW Supply line)
- (g) "S" locations are added to the excavation candidate list and evaluated for excavation, further inspection, refurbishment and repair during subsequent excavation seasons. The six "S" locations found by TWI in 2003 are listed here:
 - ID #15 (6" 1A Test Line) abandoned in '03 due to extensive internal under deposit corrosion.

- ID #314 (12" 2BPO) was excavated in 2003, scheduled for replacement in 2004.
- ID #331 (12" 2DPO) will probably be excavated in 2004.
- ID #159 (18" 1YRPO) will not be excavated in 2004 because of its large corrosion allowance.
- ID #165 (6" 1A Test) abandoned in '03 due to extensive internal under deposit corrosion.
- ID #573 (30" SW Supply line) will probably not be excavated in 2004 due to a low internal and external corrosion risk factor and the possibility this line will be smart pigged in the near future.

3.1.e (3) Results of Crossing Digs

Eight cased pipes were excavated in 2003:

- Two of the eight pipes had repair recommendations issued. One pipe was found to be derated below the design pressure of the pipe and it was replaced in 2003. The other is not derated yet and is scheduled for replacement in 2004.
- Six of the eight pipes excavated and inspected did not require de-rating, repair, or replacement. Only minor damage was found.

For all eight cased pipes that were excavated in 2003, the insulation was refurbished and the pipe wrapped with Densyl tape to prevent further corrosion.

3.1.f Other Structural Concerns

Subsidence:

Existing Well Upgrade Program:

- In 2003, 22 floors with riser piping supports were installed in well houses at Drill Sites 1D, 2A, 2K, 2T, and 3O. Well house floors are supported by the well conductor and provide table riser piping supports.
- In 2003, 65 heat tubes were installed at Drill Sites 1C, 1D, 3F, 3G, 3J, and 3Q. Heat tubes are used to keep the ground frozen or to re-freeze the ground where it has been thawed.

New Wells & Producer to Water Injection Well Conversions

- In 2003, ten new wells brought on line had heat tubes and floors with permanent pipe supports installed. In 2003, 43 new wells were installed with insulated conductors.
- In 2003, all 13 existing producers converted to water injection wells were upgraded to include heat tubes and conductor-supported floors.

Wind-Induced Vibration:

- As a result of the Drill Site (DS) 2X 8" MI line failure that occurred in December 2001, Kuparuk performed a field-wide evaluation of the need for vibration dampeners on existing pipelines. The line that failed is oriented one-degree outside the design wind direction envelope designated for Kuparuk in 1991. Based on this field-wide evaluation, tuned vibration absorbers (TVA's) have been installed on all the lines identified with pipeline sections that did not have WIV mitigation (2B, 2U, and 3G) and that fall within the design wind-direction envelope, with the exception of three lines at DS 3N. The three lines at DS 3N are on the periphery of the design wind-direction envelope and were selected for monitoring to better understand variables associated with WIV and to further validate the orientation of design wind-direction envelope. All hardware has been installed and all equipment has been functionally checked out. Final programming of the data logger will be completed this spring. Once completed, data such as line movement frequency, line movement amplitude, wind speed, and wind direction will be collected for approximately 18 months. The data will then be used to develop a better understanding of the effects of the variables on the propensity for WIV on lines oriented on the periphery of the current design wind-direction envelope.
- An annual inspection of all pipeline vibration dampener (PVD) locations is conducted to verify integrity of the PVD's. This information is sent to the facilities for corrective action. Typically, corrective action consists of replacement of worn elastomers and reinstallation of PVD weights.

3.1.g Corrosion and Structural-Related Spills/Incidents:

- 3GFBWI cross country sea water injection line leaked because of internal weld area attack in March of 2003 - The eight-inch line providing sea water to drill sites 3B, 3F and 3G failed because of internal corrosion in a circumferential weld. Total spill volume was 5,600 gallons of sea water on the tundra. Similar damage was found on several other welds and the line was de-inventoried and abandoned in place. None of the other 27 water injection lines inspected by RTR in 2003 had this type of damage.
- 3HAMIPO cross county produced crude oil line leaked because of internal deadleg corrosion in July of 2003 - The two-inch drain line branch off the main line bringing crude oil from drill sites 3I, 3M, 3A and 3H failed because of stagnant flow conditions. The spill volume was less than one gallon on the CPF3 gravel pad. Similar damage has been found on several deadlegs at Kuparuk. There is an ongoing effort to inspect all similar deadlegs.
- 2TABASCOPO cross county produced crude oil line leaked because of internal deadleg corrosion in November of 2003 - The 10" line bringing crude oil from DS 2Tabasco failed because of stagnant flow conditions. The spill volume was less than one gallon on the 2T gravel pad. Similar damage has been found on several deadlegs at Kuparuk. There is an ongoing effort to inspect all similar deadlegs.
- No leaks were caused by external corrosion in 2003.
- No leaks were caused by wind-induced vibration in 2003.
- No leaks were caused by subsidence in 2003.
- On May 24th, 2003 workers driving on the Meltwater/Tarn access road noticed a failure of the Meltwater/Tarn pipeline supports. Investigation revealed that the fillet welds connecting the vertical support member (VSM) cap plate to the horizontal support member (HSM) on 13 pipeline supports (VSM/HSM 997 thru 1025 in the Miluveach River drainage area) had failed causing the four supported pipelines to move from their original as-built positions. There was no release from any of the affected pipelines (24-inch and 16-inch produced oil pipelines, a 12-inch water injection (WI) pipeline, and an 8-inch miscible injectant pipeline), and there was no damage to the tundra or environment.

A qualitative and quantitative assessment of the pipelines by the Field Mechanical/Piping Engineer determined that the sustained stress loads (internal pressure, self-weight, etc.) were within design limits of the piping system for every case evaluated. Based on the combination of favorable qualitative and quantitative results, the pipelines were lifted back into their original centerline positions. No repairs to the pipelines were necessary and temporary cribbing pile installation, to both support and secure the pipelines, were completed without incident.

Initial examination by Engineering Staff personnel indicated fatigue cracking in 12 of the 13 fillet-welds connecting the VSM cap plate to the HSM. The fatigue loading resulted from a combination of wind-induced vibration (WIV) on the pipelines, and forces created by hydraulic slugs in the production pipelines. From a dynamic/cyclic load design basis, selection of a fillet weld as the primary load connection proved to be less robust than anticipated. Upon evaluating support structure designs from past North Slope projects, it was concluded that use of balanced, non-cantilevered support with pre-stressed bolted connections has proven to be the optimal design configuration for all loading conditions (static and dynamic) encountered in a HSM/VSM support structure's lifetime. As such, this type of design has been adopted as a best practice to be implemented to insure that this type of failure is avoided for future support structure design.

Post-failure, knee-braces were installed on the unbalanced side of the Meltwater/Tarn pipeline system support structure for the approximate 1,100 remaining VSM/HSM supports. This construction effort is nearly complete with all remaining locations, based on accessibility issues over open water, to be completed once winter tundra travel is permitted.

From a field-wide survey, similar welded support installations were discovered on two relatively-short pipelines. However, an engineering analysis confirmed that these supports are fit-for-service under the specific loading conditions characteristic of each pipeline configuration.

Figures 8 and 9, and Figure A1 in Appendix A show the number of leaks and the volumes of leaks as a function of time. Figure 8 depicts the leaks caused by internal corrosion for the well lines. Figure 9 depicts the leaks caused by internal corrosion for the cross-country lines. Figure A1 shows the leaks caused by external corrosion for cross-country lines, well lines, and below-grade piping locations.

3.2 Year 2004 Forecast

3.2.a Monitoring & Mitigation

- Test four additional new inhibitor formulations; first test will be Baker Re-5273 at DS3R. Additionally, we are discussing a possible field-wide test of concentrated blend of Champion RU-276 for the summer months.
- Test schmoo-be-gone in the water injection system for DS1E. Chemical is currently being mixed at Great Western in Fairbanks.
- Consider wellhead chemical injection systems for the production well lines at two more Drill Sites.
- Continued analysis of the CPF2 mixed water and associated systems to determine the cause of higher corrosion rates and possible mitigation options.

3.2.b Well Line Inspection

Our baseline inspection of all six-inch OD, 0.312" and 0.375" wall-thickness well lines that are six years of age or older was completed in 2003. Our recurring inspection program will start in 2004. No line in active oil service will go longer than 10 years without an inspection.

3.2.c Cross-Country Line Inspection

The following enhancements/modifications are planned for 2004:

- Our baseline RTR inspection of all CC lines requiring inspection was completed in 2003. Our recurring inspection program will start in 2004. No line in active oil service will go longer than 10 years without an inspection.
- Our baseline inspection of all elevation-change elbows scheduled as part of the Cross-Country Line Turbulent Flow Survey was completed in 2003. Based on 2003 inspection findings we will add water injection lines to the scope of work for 2004.

3.2.d External (Weld-Pack) Program

Complete evaluation of the initial CUI Buffer Spike test and determine the way forward.

Cross-country lines over tundra:

- Complete baseline TRT inspections on the remaining 711 CUI locations that were identified by the walk down verification survey completed in 2003.
- Complete recur TRT inspections on approximately 2210 CUI locations; use results to help fine-tune the prioritization scheme for future recurring inspections. Continue to monitor Denso tape protocol.
- Complete approximately 100 TRT inspections on the Tarn weld pack design established in 1997.
- Complete visual inspections of ten previously Medium Wet weld packs in saddles on large diameter sea water lines. Strip, inspect and refurbish these directly without performing TRT inspections because of the lengthy shot times involved.

For cross-country lines on-pad, inspect the remaining weld packs without a baseline inspection (approximately 500) to meet the goal of YE 2004 completion.

For well lines, inspect more than 50% of the remaining weld packs without a baseline inspection. This supports the goal of YE 2005 completion.

3.2.e Below Grade Piping Program

- Visually inspect all of the priority one and two cased lines. The appropriate CPAI field department will be notified of any corrective actions that need to be taken early enough to complete clean out and re-inspection during the summer.
- Continue recurring PTI/TWI inspections of priority one cased lines.
- Excavate, inspect, refurbish, and repair (as necessary) five-to-nine lines in road crossings.
- Continue to work with TWI and ConocoPhillips R&D to refine inspection data reduction and interpretation.

3.2.f Other

- Continue enhancements to the Kuparuk Corrosion Database.
- Continue Alpine piping layout and piping information database development.
- Continue to evaluate, and prioritize subsidence mitigation efforts at the existing drill sites.

APPENDIX A

Table A1. Three-phase Production Cross-Country lines with corrosion rates that exceeded targets and the action that was taken.

Common Line	Coupons	Probe Rate	Insp Incr	Action Taken
1EPO			x	Actual CI Rate increased, CI pump repaired
1L10 ^o PO	x			Target CI Rate increased
1RPO	x			No CI change, due to temp CI test
2EPO	x			Target CI Rate increased
2GPO			x	Target CI Rate increased
2TPO		x		Target CI Rate increased
2TAMKHPO			x	Target CI Rate increased
2UPO			x	Target CI Rate increased
2WUPO	x			Target CI Rate increased
2XPO			x	Target CI Rate increased
3HPO	x			Target CI Rate increased
3HAMIPO		x		Target CI Rate increased
3MIPO	x			Target CI Rate increased
3BFGSPO		x		Target CI Rate increased
3CPO	x			Target CI Rate increased
3IPO	x			Target CI Rate increased
3QRONKPO	x	x		Target CI Rate increased
3KPO	x			Target CI Rate increased
3OPO		x		Target CI Rate increased
3QRONKCPO		x		Target CI Rate increased
3QROPO	x			Target CI Rate increased
3WOto1	x			Target CI Rate increased




Figure A1. Leaks, saves, number of weld packs inspected with TRT, and volumes of leaks as a function of time.

Note: The leak in 2001 due to external corrosion was located in a weld pack in a below-grade piping segment, and as such, would not have been detected by the TRT inspection program. The location had not yet received PTI/TWI inspection.

APPENDIX B Glossary

Equipment Classification:

- **Well Line** – Pipe from the wellhead to the Drill Site manifold. For production wells, a well line handles the flow from a single well prior to commingling with fluids from other wells and transportation to the Central Processing Facility. For water injection wells, a well line handles the water flow going from a common manifold to a single wellhead.
- **Cross-Country Line** – Pipe from the Drill Site manifold to the Central Processing Facility (CPF).
- **Below-Grade Location** – That portion of a single pipeline, which crosses underneath a road or other earthen feature at a single location. The linear extent of the location consists of the length of pipeline between casing ends.

Service Definitions:

- **Three-phase Production** – Basic reservoir fluids (oil, water, and gas) produced from down hole through to the CPF. Typically sees changes in temperature and pressure only from reservoir changes and are essentially un-separated.
- **Seawater (SW)** – Water from the Beaufort Sea that has been treated at the Seawater Treatment Plant (STP). Note that seawater treatment at the Kuparuk STP consists of filtration, oxygen stripping using produced gas, and biociding.
- **Produced Water (PW)** – The water separated at the CPF from three-phase production.
- **Mixed Water (MW)** – Produced water and seawater that have been commingled.
- **Gas** – Generic term for the different gas systems that transport dry (no liquids) gas between facilities. Includes fuel gas, artificial lift gas, and miscible Injectant.
- **Produced Oil** – The liquid hydrocarbon separated at the CPF from three-phase production.

Inspection Technology:

- **CRM** – Corrosion rate monitoring.
- **UT** – Ultrasonic testing
- **RT** – Radiographic testing
- **RTR** – Real time radiographic testing
- **TRT** – Tangential radiographic testing
- **PII** – Profile Technologies Inc. (Electro magnetic inspection)
- **TWI** – The Welding Institute (Long range UT)
- **KDR** – Known damage recur inspection
- **Leak** – Through-wall pipe damage that causes loss of product. Product volume may not be sufficient to be classified as a "spill".
- **Save** – When the Corrosion Group recommends a repair before a leak occurs.
- **Below Grade (priority 1)** – These are pipes with a higher probability and consequence of failure. In general they have larger diameters and higher pressures and would probably cause damage to the environment or cause safety concerns if they leaked.
- **Below Grade (priority 2)** – These are pipes with a lower probability or consequence of failure. In general, these have smaller diameters and lower pressures and would probably cause little, if any, environmental damage or safety concern if they leaked. Examples include un-insulated dry gas lines and flare lines.
- **Below Grade (priority 3)** – These are pipes with a low probability and consequence of failure. Examples include decommissioned pipes, pipes in fresh or fire water service and pipes constructed of corrosion resistant materials. In addition, they contain product that would cause little, if any, environmental damage or safety concern the pipe leaked.

2004



**Greater Kuparuk Area (GKA)
Western North Slope (WNS)
Corrosion Programs Overview**

March 31, 2005

*Commitment to Corrosion Monitoring
5th Annual Report to the Alaska Department of Environmental Conservation*

Prepared by
ConocoPhillips Corrosion Team

Table of Contents

1.0 Overview

2.0 Significant Enhancements to Corrosion Programs

3.0 Greater Kuparuk Area (GKA) Program Status Summary

3.1 Year 2004 Overview

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other Structural Concerns
- g. Spills/Incidents

3.2 Year 2005 Forecast

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other

4.0 Western North Slope (WNS) Program Status Summary

4.1 Year 2004 Overview

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other Structural Concerns
- g. Spills/Incidents

4.2 Year 2005 Forecast

- a. Monitoring & Mitigation
- b. Well Line Inspection
- c. Cross-Country Line Inspection
- d. External (Weld-Pack) Program
- e. Below Grade Piping Program
- f. Other

Appendix A Glossary of Terms used in this Report

1.0 OVERVIEW

There are over \$4 Billion in capital assets in the Greater Kuparuk Area (GKA). The internal corrosion potential in Kuparuk lines continues to rise as water production and H₂S levels increase. Additionally, an external corrosion potential exist where moisture penetrates and is trapped in insulation. Effective management of corrosion at Kuparuk is critical to maintain environmental and facility integrity, reduce field operating costs, and to extend the life of the field infrastructure to meet future needs.

Alpine is ConocoPhillips' newest development and the largest onshore oil field discovered in North America in the past decade. Alpine has a nominal processing capacity of 120,000 BOPD. The Alpine development produces from a pad area of 97 acres, and has two Drill Sites; two additional satellite drill sites are being built. The corrosion management system used at Kuparuk is being applied to the Alpine field.

The purpose of this 5th Annual Report is to communicate the details of the individual programs that implement the ConocoPhillips Alaska Corrosion Strategy. In addition to the requirements of the North Slope Charter Agreement between ConocoPhillips Alaska, Inc., BP Exploration (Alaska), and the Alaska Department of Environmental Conservation, previous reporting requirements pertaining to the Below Grade Piping Program will be incorporated into this and future North Slope Charter Corrosion Reports.

A glossary of terms used in this report is included as Appendix A.

2.0 SIGNIFICANT ENHANCEMENT TO CORROSION PROGRAMS

In 2004 we implemented linear array testing which allowed us to inspect all large-diameter cross country water lines that could not be inspected with conventional Real Time Radiography (RTR), with the exception of the 30-inch and the two 24-inch sea water supply lines. This technology allowed us to greatly increase our inspection coverage of 12 water injections lines with diameters of 12" to 16".

3.0 Program Status Summary - Kuparuk

3.1 Year 2004 Overview

3.1.a Kuparuk Monitoring & Mitigation

In 2004 we had several significant accomplishments:

- Tested four new corrosion inhibitor formulations.
- Started testing of schmoob-be-gone (SBG) in the DS1E water injection system to evaluate mitigation effectiveness.
- Installed wellhead corrosion inhibitor injection systems for production well lines at three drill sites.
- Improved the existing biocide treatments of the water injection system at CPF2.

Average general and pitting coupon corrosion rate data for Year 2004 are presented in Tables 1 and 2.

Table 1. Average general corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average General Corrosion Rate, mpy (target=<3)	Number of Lines with Conformant General Corrosion Rates	Percent of Lines with Conformant General Corrosion Rates
Three-phase Production Cross-Country Lines	61	0.09	61	100
Seawater Cross-Country Lines	2	2.6	1	50
Mixed Water Injection Cross-Country Lines	22	1.1	19	86
Production Well Flow Lines	501	0.2	494	99
Mixed Water Injection Well Flow Lines	644	0.8	593	92

Table 2. Average pitting corrosion rates for corrosion coupons by service category.

Asset Group	Number of Lines with Coupons Analyzed	Coupon Average Pitting Corrosion Rate, mpy (target=<10)	Number of Lines with Conformant Pitting Corrosion Rates	Percent of Lines with Conformant Pitting Corrosion Rates
Three-phase Production Cross-Country Lines	61	4.5	53	87
Seawater Cross-Country Lines	2	5.1	2	100
Mixed Water Injection Cross-Country Lines	22	26	11	50
Production Well Flow Lines	501	1.5	471	94
Mixed Water Injection Well Flow Lines	644	9.3	442	69

Note: See graph and associated discussion on Figures 1 through 5 of this report.




Figure 1. Three-phase Production Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Three-phase Production Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 1 suggest that general corrosion is under control. The data presented in the Tables 1 and 2 and in Figure 1 include corrosion coupon data from the wet oil lines starting at CPF3 and going to CPF1 and CPF2.

Recurring CRM inspections also support the conclusion that corrosion is under control in the three-phase production cross-country lines. In 2004, 587 corrosion-rate monitoring (CRM) inspections were conducted, with two minor increases found. Other internal inspection data also support the CRM data conclusions and are discussed in section 3.1.c, below.

Where corrosion rates exceeded targets, corrosion inhibitor concentrations were increased and/or the amount of inspection was increased excluding: one corrosion inhibitor test location (2WUVPO); and one location that had increased inspection damage over a 12-month period and that had its corrosion inhibitor concentration increased at the end of 2003 (1L10PO). In 2004, coupon or probe corrosion rates exceeded targets on fifteen lines and action was taken on all fifteen of these lines. In 2004, inspection results indicated minor corrosion had occurred on six lines; corrosion inhibitor concentrations were increased in four of these lines. A complete listing of the lines with coupon/probe corrosion rates that exceeded targets and/or where inspection indicated increased damage is given in Table 3.




Figure 2. Seawater Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Sea Water Cross-Country Lines: The monitoring data summarized in Kuparuk Tables 1 and 2 and presented in Figure 2 above, shows the average corrosion rates for the sea water cross-country line coupons remained under thresholds in 2004.




Figure 3. Water Injection Cross-Country Line Coupons – general and pitting corrosion rates as a function of time.

Mixed Water Injection Cross-Country Lines: The monitoring data summarized in Kugaruk Tables 1 and 2 and presented in Figure 3 show that average general corrosion rates are below the threshold, but that pitting rates for the field are above the threshold. Closer analysis of the data shows that the average pitting rate excluding CPF2 locations is under the threshold. Coupon results are used to prioritize inspection efforts. During the second half of 2004, equipment was installed and procedures were implemented to provide enhanced biocide treatments at CPF2. The first quarter 2005 coupon pulls from CPF2 show that pitting rates are lower than the 2004 average, but are still above threshold. In addition to the biocide treatment enhancements, an additional 80K BWPD of SW has been added to CPF2. This will increase line velocities and is anticipated to help reduce the under-deposit corrosion seen on many of these coupons.




Figure 4. Three-phase Production Well Line Coupons – general and pitting corrosion rates as a function of time.

Three-phase Production Well Flow Lines: While the monitoring data summarized in Kupařk Tables 1 and 2 and presented in Figures 4 and 5 suggest that corrosion rates are below targets, inspection data indicate that higher corrosion rates have been experienced historically. The well line inspection data are discussed in section 3.1.b below, and are a good example of why monitoring data alone cannot be relied upon to characterize corrosion in a given system. For three-phase production, coupons monitor free flowing fluid and have not shown the predominant, under-deposit corrosion mechanism.




Figure 5. Water Injection Well Line Coupons - general and pitting corrosion rates as a function of time.

Water Injection Well Flow Lines: As discussed in section 3.1.b below, the well line inspection data on water injectors show that there are a significant number of corrosion related repairs. The water feeding this system is treated at the facilities with biocide and is discussed under Figure 3 - Water Injection Cross-Country Line Coupons

Mitigation




Figure 6. Field-wide Corrosion Inhibitor Use.

For the Kuparuk field, Figure 6 shows the actual number of gallons of corrosion inhibitor pumped per day, the recommended number of gallons of corrosion inhibitor per day, and the percent difference between the two. The average deviation for the year was -0.85% . The larger variation seen in the November and December 2004 data was caused by the extreme weather. The lower usage seen in May through August was due to pumping a more concentrated blend of the same field-wide corrosion inhibitor (the concentration of active components in both blends is the same).

The mitigation program is described in the inhibitor feedback flow chart, Figure 7 below. Reasons for changes to target inhibitor concentrations are given in Table 3 below.

Kuparuk Inhibitor Feedback System




Figure 7. Corrosion Inhibitor Feedback System.

Table 3 Three-phase Production Cross-Country lines with corrosion rates that exceeded targets and the action that was taken.

<u>Common Line</u>	<u>Probes</u>	<u>Coupon</u> <u>s</u>	<u>Inspectio</u> <u>n</u>	<u>Action Taken</u>
1-2ZPO			x	Increase Target PPM
1DPO		x		Increase Target PPM
1L1UPO			x	Hold (see Fig. 1 discussion)
2APO		x		Increase Target PPM
2BPO			x	Increase Target PPM
2NPO		x		Increase Target PPM
2TAMKHPO			x	Increase Target PPM
2WUVPO			x	Hold until after 50B Test
3HPO		x		Increase Target PPM
1BPO	x			Increase Target PPM
1CPO	x			Increase Target PPM
1RPO	x	x	x	Increase Target PPM
2EDPO		x		Increase Target PPM
2TPO	x	x		Increase Target PPM
3CPO		x		Increase Target PPM
3KPO		x		Increase Target PPM
3MIPD		x		Increase Target PPM
3RPO		x		Increase Target PPM
3RQONKPO		x		Increase Target PPM
3WO to CPF2		x		Increase Target PPM

3.1.b Well Line Inspection

One notable accomplishment in 2005 was that we met our primary 2004 goal by completing interval surveys on 132 well lines.

As indicated in Figure 8 below, repair recommendations were initiated on 24 lines (16 water injection, 8 production) in 2004 because of internal corrosion damage. Except for the leak, the corrosion mechanisms were all underdeposit corrosion. The leak, determined not to be an ADEC-reportable spill, was in a water injection line and was caused by erosion associated with a straightening vane pack. More information on the leak can be found in section 3.1.g.




Figure 8. Summary of Well Line Internal Corrosion Inspections – RT footage, leaks, and saves as a function of time.

ConocoPhillips

The 2004 results from the RTR surveys, manual RT, and manual UT are summarized in the following three tables.

• **RTR of Well Lines:**

Service	Feet Inspected	Number of Lines Inspected
Three-phase Production	10,217	56
Water Injection	7,530	44
Total	17,747	100

The 2004 RTR well line data indicated no new damage trends. The number of lines inspected by RTR decreased from previous years because we completed our initial baseline inspection in 2003 and started our interval recur program in 2004.

• **Manual RT of Well Lines:**

Service	Number of Lines Inspected	Number of Radiographs	Number of Repeat Radiographs	Number of Repeat Radiographs with Increases	% Of Repeat Radiographs with Increases
Three-phase Production	196	898	386	16	4
Water Injection	111	1,017	179	16	9
Total	207	1,915	565	32	6

The 2004 manual RT well line data indicated no new damage trends. The number of lines inspected by RT decreased from previous years because we completed our initial baseline inspection in 2003 and started our interval recur program in 2004.

• **Manual UT of Well Lines:**

Service	Number of Lines Inspected	Number of UT Inspections	Number of Repeat UT Inspections	Number of Repeat UT Inspections with Increases	% Of Repeat UT Inspections with Increases
Three-phase Production	170	1,442	1,254	93	7
Water Injection	69	512	384	29	8
Total	239	1,954	1,638	122	7

The 2004 manual UT well line data indicated no new damage trends. The number of lines inspected by UT decreased from previous years because we completed our initial baseline inspection in 2003 and started our interval recur program in 2004.